

Hydrographic Survey Review Panel



Fleet Issues and
Fleet Recapitalization Plan Update
RADM Jonathan Bailey, NOAA
5/5/2010




Office of Marine and Aviation Operations

Overview


- Fleet Issues
 - Budget
 - Status of \$100M ARRA Funding
 - Fleet Maintenance
 - Crew Retention
 - Utilization Comparison
- Fleet Recapitalization Plan – FSVs, Hassler, and NSVs
 - Current and Future Acquisition Process
- Questions



NOAA OMAO Budget



Operating Days



Status of ARRA Funding

- Stimulus Package – American Recovery and Reinvestment Act (ARRA)
 - Vessel Maintenance and Repair (\$20M)
 - Major Repair Period (MRP) for Rainier (\$5.78M, \$6.1M PAC)
 - Major Repair Period (MRP) for Oregon II (\$4M)
 - Drydock repair for five other vessels
 - Vessel Construction (\$73.6M)
 - Construction of FSV 6, fifth vessel in the Dyson Class




Fleet Maintenance

- \$17M Maintenance Line for 18-20 Ships
- Implementing a fleet maintenance management system
 - Maximize ship availability for mission use
 - Provide tech/tools/training/documentation to analyze existing conditions and enhance maintenance planning/execution
- Preventive Maintenance baseline review and class standardization (T-AGOS, FSV, NSV)
- Personnel management (MOC Crew Relief Pool) integral in full lifecycle management plan




Crew Recruiting & Retention

Vacancy Rate of Permanent Ship Billets




Crew Recruiting & Retention

Fleet Attrition Rate




Utilization Comparison




*Slide Provided by OCS 2009 Field Season Debrief





Ship Recapitalization Plan FY 2010 to FY 2024

■ Ecosystems
 ■ Commerce & Transportation
 ■ Climate
 First/last year of operations
 Chartered support



* David Starr Jordan missions accomplished by Miller Freeman and McArthur II until Shimada begins operations in FY 2010, then FSV6 in 2013.

Fishery Survey Vessels

- Two (i.e., *Oscar Dyson* and *Henry B. Bigelow*) of seven planned acoustically-quiet Fisheries Survey Vessels (FSVs) are currently conducting operations.
- Two more FSVs (i.e., *Pisces* and *Bell M. Shimada*) expected to be fully operational in FY2010.
- \$3M included in FY2011 President's Budget to continue design work for FSV 5.
- FSV 6 contract awarded April 22, 2010.



Ship	Homeport	Commissioning Date
<i>Oscar Dyson</i> (FSV 1)	Kodiak, AK	2005
<i>Henry Bigelow</i> (FSV 2)	Newport, RI	2007
<i>Pisces</i> (FSV 3)	Pascagoula, MS	2009
<i>Bell M. Shimada</i> (FSV 4)	Seattle, WA Newport, OR	2010
FSV 5 (shallow draft)	Pascagoula, MS	2015
FSV 6	San Diego, CA	2013
FSV 7	Newport, OR	2018



SWATH: Ferdinand R. Hassler




NOAA Survey Vessels (NSVs)

- Six additional multi-mission NOAA Survey Vessels (NSVs) are planned to be placed in service between 2018 and 2024
 - NSVs will replace:
 - Two hydrographic survey vessels
 - Four fisheries/ecosystem research vessels
- One currently active ship (*Ka'imimoana*) will undergo a service-life extension (approx. 2020)
- Phase II Recapitalization Plan being drafted to:
 - look at innovative, cost effective ways to collect in situ data
 - consider new concepts of operations which incorporate new technology, i.e., autonomous platforms (airborne, surface, underwater, etc.)



Paths for Machinery Noise

- Airborne
- First Structureborne
- Secondary Structureborne
- U/W Radiated Noise




Genset Factory Acceptance Test

10% of genset mass in each block



FRV-40 – Isolated Auxiliaries




FRV-40 – Pipe Clamps



Propeller Noise – Cavitation...

... is the vaporization of water due to a decrease of the local pressure. This generates millions of very small vapor bubbles whose collapse generates significant underwater noise.





NSWCCD design - GFI

10 kts

11 kts

G:\audio\74_short_11knt.wav

12kts

Even a little marine growth will cause cavitation below 11 knots.



Office of Marine and Aviation Operations

Slide Provided by NCE



Ship Acquisition Process

Planning Process

- Constraints
 - No input from participating organizations
 - No reflection on cost, technical and schedule feasibility
- Improvements
 - Ensure realistic cost estimates, timelines and funding

Funding

- Constraints
 - No funding for planning activities prior to PPBES execution
- Improvements
 - Fund participating organizational entities
 - Fund PAD to lead planning efforts prior to PPBES execution

Design Development

- Constraints
 - Acquisition timeline too short for adequate design development
- Improvements
 - Incorporate a contract design stage in all new ship design programs



Ship Acquisition Process

Cost Estimating

- Constraints
 - Currently rough-order-of-magnitude
 - For new designs, no models available
- Improvements
 - Develop cost estimation models
 - Train personnel to develop these models as needed

Life Cycle Management

- Constraints
 - Estimates usually based on historical data, creating future funding deficits
- Improvements
 - Life cycle planning early in the design phase
 - Concept of operations as starting point



Four Step Design Process

Concept Design

- Validate performance requirements are achievable
- Develop single design solution

Preliminary Design

- Engineering analyses and design studies
- Establish ship size, configuration, space allocations

Contract Design

- Contract package allowing shipbuilders to prepare bids
- Part of the acquisition strategy

Detail Design

- Detailed construction drawings and equipment specifications
- Occurs after the contract has been awarded
- Performed by the shipbuilder



Questions



Canadian Car Wash

